

To: 1 070930  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

3-26  
API NUMBER 13- 135-20,795-00-00 299  
NW SE, SEC. 15, T 17 S, R 24 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5086  
Operator: Pintail Petroleum, Inc.  
Name & Address: 412 E. Douglas,  
Wichita, KS 67202

1980 feet from S section line  
1980 feet from E section line

Lease Name Neyer "CB" Well # 1  
County Ness 148.52  
Well Total Depth 4570 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 263

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SMD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635  
Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 2:30 p.m. Day: 26 Month: 3 Year: 19 91

Plugging proposal received from Gary Burke  
(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 5 1/2" at 4568' w/75 sx cement, PBTD 4530', Perfs at 4499-4507'  
1st plug sand back to 4450' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump 10 sx gel and 50 sx cement at 1760',  
3rd plug pump 80 sx cement at a minimum of 1050',  
4th plug at 280' with 40 sx cement, 5th plug at 40' with 10 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 6:30 p.m. Day: 26 Month: 3 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 4350' and dumped 5 sx cement on top of sand through bailer,  
2nd plug shot casing at 1127' and pumped 80 sx cement,  
3rd plug shot casing at 737' and pumped 50 sx cement,  
4th plug pulled to 280' and pumped 40 sx cement,  
5th plug pulled casing and topped off with 10 sx cement.

Remarks: Used 60/40 Pozmix 8% gel by Allied. Recovered 737' of 5 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 4-9-91  
INV. NO. 31423

Signed Dan Boone (TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION  
APR 03 1991  
04-03-1991