

1060326

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-22,547-00-00
150' S of
E/2 NE NW, SEC. 15, T 17 S, R 24 W/E
4620 feet N from SE Corner of
4470 feet W from SE Corner of
section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5011
Operator: Viking Resources
Name &
Address 217 East William
Wichita, KS 67202-4005

Lease Name Noll Well # 1
County Ness
Well Total Depth 4443 144.40 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 260

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050
Address Box 347, Chase, KS 67524

Company to plug at: Hour: 1:00 pm Day: 5 Month: September Year: 19 84

Plugging proposal received from Mallard Kelso
(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 5 1/2" set at 4438' Open Hole 4338' - 43'

1st plug sand back to 4370' and dump 5 sx cement on top of sand through bailer
2nd plug pump 3 sx hulls, 15 sx gel, 70 sx cement, 15 sx gel, 1 sack hulls and 125
sx cement.

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:15 pm Day: 5 Month: September Year: 19 84

ACTUAL PLUGGING REPORT 5 1/2" set at 4438' Open Hole from 4338' - 43'

1st plug sanded back to 4370' and dumped 5 sx cement on top of sand through bailer,
2nd plug pumped 3 sx hulls, 15 sx gel, 70 sx cement, 15 sx gel, 1 sack hulls and 125
sx cement.

Maximum pressure 800 psi and shut in pressure 200 psi

SEP 11 1984
09-11-1984
CONSERVATION DIVISION
Wichita, Kansas

Remarks: They recovered 3009' of 5 1/2" casing. Used 60/40 Pozmix 2% gel 3% cc by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED

(10/1/84) observe this plugging.

DATE 9-17-84

Signed Paul A. Luthi SQ
(TECHNICIAN)

INV. NO. 3697