

1 050857

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-22,032-a-00-01
NE NW SW, SEC. 24, T 17 S, R 24 W/EX
2310 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4656

Lease Name Bondurant "G" Well # 1

Operator: Davis Petroleum, Inc.

County Ness 150.15

Name & Address R.R. 1, Box 183 B

Well Total Depth 4620 feet

Great Bend, KS 67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 411

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing Co, Inc. License Number _____

Address P.O. Box 628, Great Bend, KS 67530

Company to plug at: Hour: 10 a.m. Day: 11 Month: 12 Year: 1986

Plugging proposal received from L.D. Davis

(company name) Davis Petroleum, Inc. (phone) 316-793-3051

were: 5 1/2" at 4620' PBD 4455' Perfs at 4419-23, 4424-29'

1st plug pump 1 sx hulls and 20 sx cement, stop plug at 4300',

2nd plug perforate 5 1/2" at 900, pump 150 sx cement - if no returns pump 100 sx cement down 8 5/8".

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12 p.m. Day: 11 Month: 12 Year: 1986

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 20 sx cement - stopped plug at 4300',

2nd plug perforate 5 1/2" at 900' and pumped down 5 1/2", got circulation out 8 5/8",

so pumped 230 sx cement down 5 1/2" to get cement to surface.

STATE CORPORATION COMMISSION

DEC 16 1986
12-16-1986
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(if additional description is necessary, use BACK of this form.)

INVOICED

(if appropriate) observe this plugging.

DATE 12-16-86

Signed Richard W. Lacey
(TECHNICIAN)

INV. NO. 15642