

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- -135-22,907-00-00

C NE, SEC. 23, T. 18, R. 24 (W/E)

3960 FEET FROM ~~WS~~ SECTION LINE

1320 FEET FROM ~~WE~~ SECTION LINE

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # 5088

LEASE NAME Rutschman WELL # 2

OPERATOR: John Jay Darrah, Jr.
NAME & 412 East Douglas, Suite One
ADDRESS Wichita, KS 67202

COUNTY Ness 149.18

WELL TOTAL DEPTH 4590 (Mississippi) FEET

CONDUCTOR PIPE: SIZE _____ FEET _____

SURFACE CASING: SIZE 8 5/8 FEET 261

ABANDONED OIL WELL _____ GAS WELL _____ INPUT WELL _____ SWD WELL _____ D&A X

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR Mallard Drilling Co., Inc. LICENSE NUMBER 5651

ADDRESS 405 Century Plaza, Wichita, KS 67202

COMPANY TO PLUG AT: HOUR: 6:00 am DAY: 2 MONTH: September YEAR: 19 85

PLUGGING PROPOSAL RECEIVED FROM Kelly Cosby

(COMPANY NAME) Mallard (PHONE) 316-263-8218

Elevation 2483'

WERE: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1794-1825'

1st plug at 1825' with 50 sx cement

2nd plug at 850' with 60 sx cement

3rd plug at 300' with 40 sx cement

solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement, 7th plug to circulate mouse hole with 10 sx cement

PLUGGING PROPOSAL RECEIVED BY Don C. Uebel
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION

SEP 6 1985

09-06-1985
CONSERVATION DIVISION
Wichita Kansas

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL _____ PART _____ NONE _____ X

OPERATIONS COMPLETED: HOUR: 9:20 am DAY: 2 MONTH: September YEAR: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1825' with 50 sx cement, 2nd plug at 850' with 60

sx cement, 3rd plug at 300' with 40 sx cement, 4th & 5th plugs - solid bridge- hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 15

sx cement, 7th plug to circulate mouse hole with 10 sx cement.

9-2-85

REMARKS: Used 60/40 Pozmix 6% gel by Allied.

I ~~(DID)~~ / DID NOT OBSERVE THIS PLUGGING.

SIGNED Don C. Uebel
(TECHNICIAN)

Rem. J.

UNVOICED

DATE SEP 10 1985

INV. NO. 10006

9-2 OCT 09 1985

CARD MUST BE TYPED

State of Kansas
NOTICE OF INTENTION TO DRILL
(see rules on reverse side)

CARD MUST BE SIGNED

Starting Date: 8 19 85
month day year 2:20

API Number 15- 135-22,907-00-00

OPERATOR: License # 5088
Name John Jay Darrah, Jr.
Address 412 E. Douglas, Suite One
City/State/Zip Wichita, Kansas 67202
Contact Person Bo Darrah
Phone 263-2243

(location) C. NE Sec 23, Twp 17, S, Rge 24
3960' Ft North from Southeast Corner of Section
1320' Ft West from Southeast Corner of Section
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5651
Name Mallard Drilling Co., Inc.
City/State Wichita, Kansas 67202

Nearest lease or unit boundary line 1320' feet.
County Ness
Lease Name Rutschman Well# 2
Domestic well within 330 feet: yes no
Municipal well within one mile: yes no

Well Drilled For: Well Class: Type Equipment:
 Oil Swd Infield Mud Rotary
 Gas Inj Pool Ext. Air Rotary
 OWWO Expl Wildcat Cable

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth
Projected Total Depth 4600 feet
Projected Formation at TD Mississippi
Expected Producing Formations Cherokee Sand

Depth to Bottom of fresh water 60 feet
Lowest usable water formation Dakota
Depth to Bottom of usable water 800 feet
Surface pipe by Alternate: 1 2
Surface pipe to be set 240' feet
Conductor pipe if any required N/A feet
Ground surface elevation 2483 feet MSL
This Authorization Expires 2-16-86
Approved By 8-16-85

certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C.C. specifications. Production String will be immediately cemented.
Date 8/15/85 Signature of Operator or Agent John Jay Darrah, Jr. Title Operator
Form C-1 4/84

Spud 8-26-85
Set - 240'

RECEIVED
STATE CORPORATION COMMISSION
SEP 6 1985
09-06-1985
CONSERVATION DIVISION
Wichita, Kansas