

To: 1 070365  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 135-21,574-00-00  
E/2 NW NE, SEC. 21, T 17 S, R 24 W/E  
4620 feet from S section line  
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5161

Lease Name Keilman "C" Well # 1  
County Ness 142.74

Operator: Palomino Petroleum  
Name & Address Route 5, Box 51-C  
Newton, KS 67114

Well Total Depth 4392 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 281

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 10:30 a.m. Day: 2 Month: 7 Year: 19 87

Plugging proposal received from Jim Rockhold

(company name) Rockhold Engineering, Inc. (phone) 316-792-2506

were: 5 1/2" at 4375' PBSD 4335' Perfs at 4282-4300'

1st plug sand back to 4225' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"  
wiper plug and pump 150 sx cement.

Plugging Proposal Received by Paul Luthi and Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:30 a.m. Day: 2 Month: 7 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 4225' and dumped 5 sx cement on top of sand  
through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released  
8 5/8" wiper plug and pumped 150 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
07-07-1987  
7 1987

Maximum pressure 700 psi and shut in 100 psi.

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied. Rec 1464' of 5 1/2 casing  
(if additional description is necessary, use BACK of this form.)

INVOICED  
I (and ~~you~~) observe this plugging.

Signed Dan Goodrow  
(TECHNICIAN)

DATE 7-7-87

INV. NO. 17429