

1 040867

7-16

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-23,824-00-00
SE NE SE, SEC. 8, T 17 S, R 24 W. XX
1650 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30742

Lease Name Tilley Well # 4

Operator: Palomino Petroleum, Inc.

County Ness

Name & Address 4924 SE 84th St.

Well Total Depth 4495 146.08 feet

Wichita, KS 67114-8827

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 221

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Mallard, J.V., Inc. License Number 4958

Address P.O. Box 1009, -McPherson, KS 67460

Company to plug at: Hour: 4:55 a.m. Day: 16 Month: 7 Year: 19 94

Plugging proposal received from Carol

(company name) Mallard J.V., Inc. (phone) 316-869-2073

Work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1762-97'

1st plug at 1800' with 50 sx cement, 2nd plug at 1200' with 80 sx cement,

3rd plug at 600' with 50 sx cement, 4th plug at 250' with 40 sx cement,

5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 7 a.m. Day: 16 Month: 7 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug at 1800' with 50 sx cement,

2nd plug at 1200' with 80 sx cement, 3rd plug at 600' with 50 sx cement,

4th plug at 250' with 40 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel # FlöSeal by Allied.

(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 7-21-94

INV. NO. 40844

7-16

Signed Stephen J. Pfeifer (TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
JUL 20 1994
07-20-1994
CONSERVATION DIVISION
Wichita, Kansas

EFFECTIVE DATE: 7-5-94

DISTRICT # 1
SEA? Yes No

State of Kansas

NOTICE OF INTENTION TO DRILL 15-135-23,824-00-00 ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 7 11 94
month day year

Spot SE NE SE Sec 8 Twp 17 S, Rg 24 East West

OPERATOR: License # 30742
Name: Palomino Petroleum, Inc.
Address: 4924 SE 84th Street
City/State/Zip: Newton, Kansas 67114-8827
Contact Person: Klee R. Watchous
Phone: (316) 283-0232

1650 feet from South / ~~NE~~ line of Section
330 feet from East / ~~SE~~ line of Section

IS SECTION X REGULAR IRREGULAR?
(NOTE: Locate well on the Section Plat on Reverse Side)

CONTRACTOR: License # 4958
Name: Mallard JV, Inc.

County: Ness
Lease Name: Tilley Well #: 4
Field Name: Dickman

Is this a Prorated/Spaced Field? yes X no
Target Formation(s): Miss

Nearest lease or unit boundary: 330
Ground Surface Elevation: 2478 feet MSL

Well Drilled For: Well Class: Type Equipment:
X Oil ... Enh Rec X Infield X Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary
... OWD ... Disposal ... Wildcat ... Cable
... Seismic: ... # of Holes ... Other

Water well within one-quarter mile: yes X no
Public water supply well within one mile: yes X no

Depth to bottom of fresh water: 50 730
Depth to bottom of usable water: 1140

Surface Pipe by Alternate: 1 X 2
Length of Surface Pipe Planned to be set: 200

Length of Conductor pipe required: None
Projected Total Depth: 4500

Formation at Total Depth: Miss
Water Source for Drilling Operations: well farm pond X other

DWR Permit #: STATE CIRCA 11/1/93
Will Cores Be Taken?: yes X no

If yes, proposed zone: 200' Alt. II Req.

If OWD: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? yes X no
If yes, true vertical depth:
Bottom Hole Location:

Exp. 12/30/94 AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.
It is agreed that the following information shall be furnished to the State of Kansas:

Pusher 5" 1/2
SPUD DATE 7.9.94 INIT. GB
LENGTH SURFACE PLANNED 200' of 888
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 888 @ 22' CONDUCTOR
ANHYDRITE T-1762 B-1792 ELEVATION
(2 1/2 3) FORMATION
TD 4195
RAN PIPE @ DV TOOL ALT II DONE
SX Y N
Arbuckle Plug @ Ft. W/ SX
Hug./Council @ Ft. W/ SX
Anhydrite Base @ 1800 Ft. W/ 50 SX
1/2 Base Anhy. @ 1200 Ft. W/ 80 SX
1/2, 1/2 Plug @ 600 Ft. W/ 50 SX
Bottom Surface @ 250 Ft. W/ 40 SX
40' Plug @ 40 Ft. W/ 10 SX
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/10 SX
WATER WELL SX (Irr. Well Pond)
TECHNICIAN SP DATE 7-11-94 Hauling
TYPE OF CEMENT 60/40/26 gel 1/4 @ Flow Seal
STARTING TIME 4:55 (AM/PM) DATE 7-16-94
COMPLETION TIME 7:00 (AM/PM) DATE 7-16-94
CEMENT COMPANY Allied

canal w/ mallard for P.O.

RECEIVED JUN 30 1994
STATE CIRCA 11/1/93
CASE NO. 06-30-1994