

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- -135-22, 430-00-00

TECHNICIAN'S PLUGGING REPORT

C SE NE, SEC. 8, T17S, R24W

2086 FEET FROM N/S SECTION LINE

554 FEET FROM W/E SECTION LINE

OPERATOR LICENSE # 5004

LEASE NAME Phelps "B" WELL # 1

OPERATOR: Vincent Oil Corporation  
NAME & ADDRESS 125 N. Market, Suite 1110  
Wichita, KS 67202

COUNTY Ness

WELL TOTAL DEPTH 4456 FEET \$144.82

CONDUCTOR PIPE: SIZE \_\_\_\_\_ FEET \_\_\_\_\_

SURFACE CASING: SIZE 8 5/8 FEET 369

ABANDONED OIL WELL \_\_\_\_\_ GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SWD WELL \_\_\_\_\_ D&A

OTHER WELL AS HEREINAFTER INDICATED \_\_\_\_\_

PLUGGING CONTRACTOR Abercrombie Drilling Inc LICENSE NUMBER 5422

ADDRESS 801 Union Center Bldg Wichita, KS 67202

COMPANY TO PLUG AT: HOUR: 10:00am DAY: 25 MONTH: August YEAR: 1983

PLUGGING PROPOSAL RECEIVED FROM Tony Martin

(COMPANY NAME) Abercrombie Drilling Inc (PHONE) \_\_\_\_\_

WERE: 60/40 pozmix 2% gel 3% cc

1st plug @ 1770' w/50sx, 2nd plug @ 810' w/50sx,  
3rd plug @ 420' w/40sx, 4th plug @ 40' w/  
solid bridge plug + 10sx, Circulate 15sx in  
the rat hole

PLUGGING PROPOSAL RECEIVED BY Richard W. Lacey  
(TECHNICIAN)

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL \_\_\_\_\_ PART \_\_\_\_\_ NONE

OPERATIONS COMPLETED: HOUR: 12:30pm DAY: 25 MONTH: August YEAR: 1983

ACTUAL PLUGGING REPORT Plugged as proposed in above paragraph  
Halliburton pumped the cement

REMARKS: \_\_\_\_\_

I (DTD / DID NOT) OBSERVE THIS PLUGGING.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 1 1983  
09-01-1983  
CONSERVATION DIVISION  
Wichita, Kansas

SIGNED: Richard W. Lacey  
(TECHNICIAN)  
INVOICED  
DATE 9-16-83  
INV. NO. 5467-W

FORM CP-213  
REV. 6-83