

1090271

4-22

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-135-20,995-0000

C NE SE, SEC. 6, T. 17 S, R. 24 W/E

1980 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5238

Lease Name Vermillion B Well # 1

Operator: Petroleum, Inc.  
Name:

County Ness 146.18

Address 301 N. Main, Ste. 900

Well Total Depth 4498 feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 282

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Petroleum, Inc. License Number 5238

Address 301 N. Main, Ste. 900, Wichita, KS 67202

Company to plug at: Hour: 9:15 a.m. Day: 22 Month: 4 Year: 1993

Plugging proposal received from Bill Daugherty

(company name) Petroleum, Inc. (phone) 316-291-8200

were: 5 1/2" at 4493' w/100 sx cement, PBD 4490', Perfs at 4394-4402'

1st plug set CIBP at 4300' with 50' of sand on top,

2nd plug load casing with water, perforate casing at 1150' and pump in 190 sx cement,

3rd plug hook onto backside and pump in 160 sx cement.

Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 9:45 a.m. Day: 22 Month: 4 Year: 1993

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4300' with 50' of sand on top,

2nd plug loaded casing with water, tested casing to 200 lbs., perforated casing at 1150' and pumped in 190 sx cement. Maximum pressure 400 psi and shut in 0.

3rd plug hooked onto backside, pumped in 60 sx cement. Maximum pressure 500 psi and shut in 450 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.  
(If additional description is necessary, use BACK of this form.)

RECEIVED  
STATE CORPORATION COMMISSION  
04-26-1993  
APR 26 1993

I (did ~~not~~) observe this plugging.

Signed Steve Middleton  
(TECHNICIAN)  
CONSERVATION DIVISION  
Wichita, Kansas

DATE 4-28-93

INV. NO. 37626 4-22