

To: 1051987  
STATE CORPORATION COMMISSION 12-11  
Wichita State Office Bldg. PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15-135-23,885-00-00  
SW SE NE, NE, SEC. 6, T 17 S, R 24 W/E  
1155 feet from NE section line  
495 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 31565  
Operator: Coyote, Inc.  
Name: \_\_\_\_\_  
Address 217 S. Broadway  
Wichita, KS 67202

Lease Name Otis Well # 1-6  
County Ness 148.34  
Well Total Depth 4565 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 206.63

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Mike's Testing & Salvage Inc. License Number 31529  
Address P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 1:30 p.m. Day: 11 Month: 12 Year: 19 95

Plugging proposal received from David  
(company name) Mike's Testing & Salvage Inc. (phone) 316-938-2943

Core: 4 1/2" at 4561' w/100 sx cement, Perfs at 4509-12'  
1st plug sand back to 4450' and dump 4 sx cement on top of sand through bailer,  
2nd plug pump 50 sx cement at 1760', 3rd plug pump 80 sx cement at 1000',  
4th plug pump 40 sx cement at 500', 5th plug pump 40 sx cement at 230',  
6th plug pump 40 sx cement at 10'.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 8 p.m. Day: 11 Month: 12 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug sanded back to 4450' and dumped 4 sx cement on top of  
sand through bailer,

2nd plug at 1760' with 50 sx cement displaced with gel,  
3rd plug at 1000' with 80 sx cement displaced with gel,  
4th plug at 500' with 40 sx cement displaced with gel,  
5th plug at 230' with 40 sx cement, 6th plug at 40' with 10 sx cement

RECEIVED  
STATE CORPORATION COMMISSION  
12-14-1995  
DEC 14 1995

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2400' of gel.  
(If additional description is necessary, use BACK of this form.)

~~INVOICE~~ observe this plugging.

Signed Richard W. Lacey  
(TECHNICIAN)

DATE 1-5-96  
INV. NO. 44415