

To: 1 090270  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

4-22

API NUMBER 15- 135-20,925-00-00

C SE NE, SEC. 6, T. 17 S, R. 24 W/EX  
3300 feet from S section line  
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5238

Lease Name Vermillion A Well # 1

Operator: Petroleum, Inc.  
Name & Address 301 N. Main, Ste. 900  
Wichita, KS 67202

County Ness 146.18  
Well Total Depth 4498 feet

Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 262

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Petroleum, Inc. License Number 5238

Address 301 N. Main, Ste. 900, Wichita, KS 67202

Company to plug at: Hour: 10:15 a.m. Day: 22 Month: 4 Year: 19 93

Plugging proposal received from Bill Daugherty

(company name) Petroleum, Inc. (phone) 316-291-8200

were: 5 1/2" at 4497' w/100 sx cement, PBSD 4490', Perfs at 4482-88'

1st plug set CIBP at 4300' with 50' sof sand on top,

2nd plug load casing with water, perforate casing at 1150' with 170 sx cement,

3rd plug hook onto backside and pump in 40 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:50 a.m. Day: 22 Month: 4 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4300' with 50' of sand on top,

2nd plug loaded casing with water, tested casing to 200 lbs., perforated casing at 1150', pumped in 170 sx cement. Maximum pressure 800 psi and shut in 100 psi.

3rd plug hooked onto backside and pumped in 40 sx cement,

Maximum pressure 500 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.  
(If additional description is necessary, use BACK of this form.)

INVOICED (did not observe this plugging.)

DATE 4-28-93

WEL. NO. 37625

4-22

Signed [Signature] (TECHNICIAN)

RECEIVED STATE CORPORATION COMM 04-26-1993 APR 26 1993 CONSERVATION DIVISION Wichita, Kansas