

1 060772

KCC
AUB

API NUMBER 15- N/A ~~135-19187-0000~~

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

~~NW SE SE~~
~~SW NE~~, SEC. ~~33~~ 32, T 17 S, R 26 W/E
SWNE

3300 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5131
Operator: Thunderbird Drilling
Name & Address: P. O. Box 18407
Wichita, KS 67202 67218
685-1441

Lease Name Castor Well # 1
County Ness 145.54
Well Total Depth 4478 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 351

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1:45 pm Day: 17 Month: January Year: 19 86

Plugging proposal received from Bob Brenneman

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" at 4467' Open Hole 11'

1st plug sand back to 4420' and dump 5 sx cement on top of sand through bailer

2nd plug pump 50 sx cement, 10 sx gel, and 100 sx cement down 5 1/2"

3rd plug pump 50 sx cement down Annulus

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:45 pm Day: 17 Month: January Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 4420' and dumped 5 sx cement on top of

sand through bailer, 2nd plug pumped 50 sx cement, 10 sx gel, and 100 sx cement down 5 1/2" casing. Pumped 50 sx cement down Annulus.

STATE CORPORATION COMMISSION
RECEIVED
JAN 27 1986
CONSERVATION DIVISION

Maximum pressure on 8 5/8" at 200 psi and shut in 100 psi

Maximum pressure 700 psi on 5 1/2" and shut in 300 psi

No Recovery - could not get casing loose. Shot at 1500', shot at 1200' and shot at 1000'

Remarks: Used 60/40 Pozmix 6% gel 3% cc by Allied.
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE JAN 30 1986

Signed Paul A. Luthi (TECHNICIAN)

INV. NO. 12192