

061150

10-21-88

API NUMBER 15-135-22,571-00-00

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NW NE NW, SEC. 21, T 17 S, R 24 W/E

4950 feet from S section line  
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5161

Lease Name Habiger-Keilman Well # 5

Operator: Palomino Petroleum  
Name & Address: Route 5, Box 51-  
Newton, KS 67114

RECEIVED

STATE CORPORATION COMMISSION

County Ness 142.35  
Well Total Depth 4380 feet

OCT 25 1988

10-25-1988

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 308

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 12 p.m. Day: 21 Month: 10 Year: 19 88

Plugging proposal received from Jim Rockhold

(company name) Rockhold Engineering, Inc. (phone) 316-792-2506

were: 5 1/2" at 4369' Perfs at 4269-73, 4283-87'

1st plug sand back to 4220' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump 3 sx hulls, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug  
and pump 150 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 12:45 p.m. Day: 21 Month: 10 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4220' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 800 psi and shut in 500 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1052' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 10-28-88

Signed Paula A. Luther (TECHNICIAN)

INV. NO. 22838