

R

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 135- 21,599 -00-00 (of this well)

Operator's Full Name Palomino & Darrah et al

Complete Address 500 Insurance Bldg., Wichita, Ks.

Lease Name Keilman "D" Well No. 1

Location SW SE NE Sec. 21 Twp. 17 Rge. (E) (W) 24

County Ness Total Depth 4422

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Strata Drlg.

Address Wichita, Ks. License No.

Operation Completed: Hour 1 A Day 11 Month 4 Year 1979

The above well was plugged as follows:

RTD 4422' 8 5/8 csg set 293' cwc Plg Mat 60/40 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 720' thru drill pipe.

Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

APR 12 1979
04-12-1979
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 4-13-79
INV. NO. 9424-W

Signed: Leo Massey
Well Plugging Supervisor