

15-135-20151-0000

Form CP-3
Rev. 6-26-62

KANSAS

V

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

06-10-1968
RECEIVED
STATE CORPORATION COMMISSION
JUN 10 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Walters Drlg. Co. et al

Complete Address: 400 Insurance Bldg., Wichita, Kansas

Lease Name Sargent-Anderson Well No. 1

Location C SW SE Sec. 7 Twp. 17 Rge. 24 (E) (W) X

County Ness Total Depth 4485

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Co. Tools

Address: License No.

Operation Completed: Hour 5:45 A Day 7 Month 6 Year 1968

The Above well was plugged as follows:

RTD 4485' 8 5/8 csg set at 208' cwc 140 sc. Cem. Mat. 100 sc 50-50 poz W/6% total gel
Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sc ceme
thru drill pipe. Heavy mud to 180' set cementing plug and displaced 20 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: R. W. Massey
Well Plugging Supervisor

DATE 6/10/68
INV. NO. 7918-W