

15-135-00029-00-01

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 16 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name R. V. Lehner

Complete Address P. O. Box 398 Ness City, Kansas

Lease Name Dinges (Washdown) Well No. 1

Location SE SE SE Sec. 2 Twp. 18 Rge. (E) (W) 26

County Ness Total Depth 4566

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated Washdown

Plugging Contractor Strata Drlg

Address Wichita, Kansas License No.       

Operation Completed: Hour 8:45A Day 13 Month 1 Year 1970

The above well was plugged as follows:

RTD 4566'. 8 5/8 csg set at 251' cwc. Cmt. Mat. 50-50 poz 6% gel.

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk cmt

thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base

of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 1/16/70  
INV. NO. 1261-W