

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 24 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Petroleum, Inc.

Complete Address 200 W. Douglas Wichita, Kansas 67202

Lease Name O'Brien "B" Well No. 3

Location SW NW SW Sec. 9 Twp. 11 Rge. (E) (W) 18

County Ellis Total Depth 3218

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Garvey Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 1.30P Day 21 Month 2 Year 1970

The above well was plugged as follows:

RTD 3218' 8 5/8 csg set at 252' cwc Cmt. Mat. 50-50. poz cmt W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 540' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo P. Muesny
Well Plugging Supervisor

INVOICED

DATE 2/25/70

INV. NO. 1493-W