

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____

LOCATION SW SE NW

SEC. 9 TWP. 11 RGE. 18

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease O'Brien O'Brien

Operator National Co-op Refg Assn Address 1910 Broadway Great Bend, Kans

Field _____ County Ellis

Total Depth 3580 Feet.

Plugging Contractor K & E Drg Co & Halliburton Co

Plugging Contractor's License No. _____

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 247' circulated with cement.

Gunned pits, circulated hole with heavy mud, set cementing plug at
400', displaced 20 sax cement through drill pipe, heavy mud to 200',
set cementing plug and displaced 20 sax cement through drill pipe,
heavy mud to 40', set cementing plug, 1/2 sack hulls and 10 sax cement
to bottom cellar.

Edwin Kelly
District Conservation Agent

1-22-58

Date _____

RECEIVED
STATE CORPORATION COMMISSION

JAN 25 1958

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 9 T 11 R 18W
BOOK PAGE 28 LINE 4