

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-135-22,068-00-00

200 Colorado Derby Bldg.
Wichita, KS 67202

Operator's Full Name JOHN J DARRAH.

Complete Address 1010 CENTRY PLAZA BLDG., WICHITA, KANS.

Lease Name AUDRY RUFENACHT. Well No. #1

Location 200'-SW-NE-SE Sec. 27 Twp. 17 Rge. 24 (East) (West)

County NESS Total Depth 4435 FE

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor HELSO CASING PULLING

Address BOX 176 CHASE, KANS. License No. _____

Operation Completed: Hour: 12:00 ^{NOON} ^{PM} Day: 3 RD Month: SEPT. Year: 19 81

Plugging Operations attended by Agent? All Part None

The above well was plugged as follows:

8 5/8" - 306 FE SD. CUL ^{11/175} ST CMT. → 4 1/2" SET @ 4426 FE ^{11/150} ST CMT.

PEEB'S OPEN HOLE 6 FE → SAND BOTTOM TO 4350 FE ^{11/4} ST CMT.

SHOT PIPE 3 TIMES → RECOVERED 2505 FE

ORDERED - 140 ST ⁵⁰ PERMIX 4% GEL - 3% CHCL. → 24 ST GEL. → 5 ST HULLS - + 8 5/8" PLUG

PUMPED IN WITH PUMP TRUCK.

PAT. IN - 4 ST HULLS - 15 ST GEL. → 1 ST HULLS → 70 ST CMT. → 9 ST GEL.

RELEASED PLUG. + 70 ST CMT. MAX PRESSURE 800 LBS

CEMENTED BY ALLERSON

STATE CORPORATION COMMISSION

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 10-28-81

INV. NO. 8079W

Signed: Maureen Johnson
Conservation Division Agent
Wichita, Kansas
SEP - 4 1981
09-04-1981
CONSERVATION DIVISION
Wichita, Kansas
+ Gilbert Shuck.