

15-135-20632-00-00  
KANSAS

Form CP-3  
Rev. 6-4-68

R

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

06-27-1972  
RECEIVED  
STATE CORPORATION COMMISSION  
JUN 27 1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Beardmore Oil, Incorporated,

Complete Address 700 One-Twenty Building, Wichita, Kansas.

Lease Name Rufenacht Well No. A-1

Location NE-NW Sec. 27 Twp. 17 Rge. (E) (W) 24

County Ness Total Depth 4495'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated     

Plugging Contractor Rains & Williamson Oil Company, Incorporated,

Address 475 Page Court, Wichita, Kansas. License No.     

Operation Completed: Hour 6:00 PM Day 25 Month 6 Year 1972

The above well was plugged as follows:

257'--8 5/8" Surface casing, cement circulated with 175 Sx.  
Top of Dakota section @ 475'.

Circulated hole with heavy mud. Pulled DP to 700' and displace 110 Cu. Ft. cement  
thru DP from 700' to 375'. Pulled DP to 280' and displaced 30 Cu. Ft. cement thru  
DP from 280' to 205'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols  
Well Plugging Supervisor

INVOICED

DATE 6/29/72  
INV. NO. 5933-W