

15-135-20519-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
08-27-1973
AUG 27 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Wichita Iron & Metals Corporation
Complete Address Box 13021 Wichita, Kansas 67218
Lease Name Schreiber Well No. 1
Location C: NE SW. Sec. 26 Twp. 17 Rge. (E) (W) 24
County Ness Total Depth 4468'
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Glenn Casing Pulling
Address Box 156 Ellinwood, Kansas 67526 License No. 686
Operation Completed: Hour 11:30 A. Day 24 Month 8 Year 1973

The above well was plugged as follows:

Total Depth 4468' 8 5/8 csg set at 415' cwc 250 sx.
5 1/2 csg set at 4460' cw 125 sx cem.
Filled 5 1/2 csg W/sd (4440-4468) dumped 5 sk cmt W/dump bailer. (4400-4440)
Cutoff and recovered 3000' of 5 1/2 csg.
Pumped down 8 5/8 csg with 15 sx gel & water--80 sx cem.--8 sx gel & water and
capped with 20 sk cmt.

I hereby certify that the above well was plugged as herein stated.

Signed: Eric J. Murray
Well Plugging Supervisor

INVOICED

DATE 8/30/73
INV. NO. 7830-W