

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number ⁵³⁰15 - 135_ 21, ~~500~~ -00-00 (of this well)

Operator's Full Name Beren Corp.
Complete Address 970 Fourth Financial Center, Wichita, Kansas
Lease Name Schreiber Well No. 1
Location C SW SW Sec. 26 Twp. 17 Rge. (E) (W) 24
County Ness Total Depth 4476'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Strata Drlg.
Address Wichita, Kansas License No.
Operation Completed: Hour 4:30 A Day 21 Month 11 Year 1978

The above well was plugged as follows:

RTD 4476' 8 5/8 csg set 335' cwc Plg. Mat. 50-50 poz 6% total gel.
Gunned pits, circulated heavy mud, set 70 sk cmt plug at 720' thru drill pipe.
Heavy mud to 300' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt plug to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

NOV 27 1978
11-27-1978
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 11-29-78
INV. NO. 8627-W

Signed: Geo. Massey
Well Plugging Supervisor