

15-135-20202-00-00

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 14 1968
CONSERVATION DIVISION
Wichita, Kansas
11-14-1968

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Imperial Oil Co.

Complete Address: 780 4th Nat'l Bldg., Wichita, Kansas

Lease Name Neyer Well No. 1

Location C SE SW Sec. 14 Twp. 17 Rge. 24 (E) (W) XX

County ness Total Depth 4560

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated:

Plugging Contractor: Co. Tools

Address: License No.

Operation Completed: Hour 5:45A Day 11 Month 11 Year 1968

The Above well was plugged as follows:

RTD 4560' 8 5/8 csg set at 277' cwc Gmt. Mat. 50-50 poz cmt. W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 900' and displaced 100 sc cmt.

thru drill pipe. Heavy mud to 270' set cementing plug and displaced 20 sc cement thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base

of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

Signed: Geo F. Massey
Well Plugging Supervisor

INVOICED
DATE 11/14/68
INV. NO. 8816-4