

15-135-2111-00-00

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION

NOV 3 1975
11-03-1975
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Walters Drilling Company
Complete Address 400 Insurance Bldg., Wichita, Kansas
Lease Name A.P.H. Well No. 1
Location C NE NE Sec. 14 Twp. 17 Rge. (E) (W) 24
County Ness Total Depth 4 515'
Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A XX
Other well as hereafter indicated _____
Plugging Contractor DNB Drlg.
Address Wichita, Kansas License No. _____
Operation Completed: Hour 5:50A Day 2 Month 11 Year 1975

The above well was plugged as follows:

RTD 4515' 8 5/8 csg set 252' cwc 150 sk. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug-at 720' thru drill pipe.

Heavy mud to 250' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 11/3/75

INV. NO. 2178-W

Signed: Res Massey
Well Plugging Supervisor