

KANSAS

Form CP-3
Rev. 6-4-68

R

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 18 1977
04-18-1977
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 135-21,314-00-00 (of this well)

Operator's Full Name Walters Drilling Co.

Complete Address 400 Insurance Bldg., Wichita, Kansas

Lease Name Lynch "B" Well No. 1

Location C NW SE Sec. 13 Twp. 17 Rge. (E) (W) 24

County Ness Total Depth 4470'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated _____

Plugging Contractor Slawson Drlg. Co.

Address Wichita, Kansas License No. _____

Operation Completed: Hour 4:30 A Day 16 Month 4 Year 1977

The above well was plugged as follows:

RTD 4470' 8 5/8 csg set 307' cwc 200 sk. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 720' thru drill pipe.

Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 4-18-77

INV. NO. 4997-W