

State of Kansas



15-051-20415-0000

ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
 STATE CORPORATION COMMISSION
 APR 21 1969
 CONSERVATION DIVISION
 Wichita, Kansas

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Kohlrus of Sage Drlg. has this

date requested permission to plug the following described well:

Mr. Kohlrus guarantees payment of the plugging fee.

Operator's full Name: Sage Drilling Co., Inc.

Complete Address: 500 Bitting Bldg., Wichita, Ks.

Lease Name: Frisbie Well No. 1

Location: NE NE NW Sec. 20 Twp. 11 Rge. (E)(W) 18

County: Ellis Total Depth 3567' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Kohlrus was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 600' and displace

70 sk cmt. thru drill pipe. Heavy mud to 240' set cementing plug and

displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sk hulls and 10 sk cmt to base of cellar. Plug rat hole

with 2 sk cmt.

Very truly yours,

Leo J. Messing
 Conservation Division Agent