

State of Kansas



15-051-20374-0000

ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 2 1969
 CONSERVATION DIVISION
 Wichita, Kansas

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Buchheister of John O. Farmer Drlg. has this date requested permission to plug the following described well:

Mr. Buchheister guarantees payment of the plugging fee.

Operator's full Name: Murfin Drlg. Co.

Complete Address: 617 Union Center Wichita, Ks.

Lease Name: Jacobs-Peavy Well No. 1

Location: App. SE NW SE Sec. 26 Twp. 11 Rge. 18 (E)(W) X

County: Ellis Total Depth 3710' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Buchheister was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 720' and displace
70 sc cement thru drill pipe. Heavy mud to 180' set cementing plug and
displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole with
2 sc cement.

Very truly yours,

Geo. J. Mueser
 Conservation Division Agent