

State of Kansas



FORM CP-2

15-051-00159-0001

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Dennis Sporing of Abercrombie Drlg. Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Foxfire Exploration Inc.

Complete Address: 105 S. Broadway, Suite 610 Wichita, Ks. 67202

Lease Name: Martin Well No. 1

Location: SW SW SW Sec. 2 Twp. 11 Rge. 19 (E) (W)

County: Ellis Total Depth: 3660'

Abandoned Oil Well Gas Well Input Well SWD Well D&A XXX

Other well as hereafter indicated: _____

Mr. Sporing was instructed to plug the well as follows:

8 5/8" 207' S.P. cuc. common.

Ordered 130 sacks 50/50 posmix 4% Gel.-3% CaI.Cl. and 8 5/8" plug.

- 1st plug @ 720' with 70 sacks cement
- 2nd plug @ 200' with 40 sacks cement
- 3rd plug solid bridge of hulls and plug @ 40' with 10 sacks cement

Circulated 10 sacks in rat hole.

Very truly yours,


Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION
FEB - 2 1962
CONSERVATION DIVISION
Wichita, Kansas