

State of Kansas



FORM CP-2

15:051-22899-0000

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Tarry Austin of Big Springs Drilling has this

date requested permission to plug the following described well:

Operator's Full Name: Murchison Oil & Gas

Complete Address: 2500 Diomand Shamrock Tower 717717 N. Harwood, Dallas, Texas

Lease Name: Ginther Well No. 1

Location: NE NW SE Sec. 35 Twp. 11 Rge. 18 (E) (W)

County: Ellis Total Depth: 3680'

Abandoned Oil Well Gas Well Input Well SWD Well D&A XXX

Other well as hereafter indicated: _____

Mr. Austin was instructed to plug the well as follows:

8 5/8"-270' S.P. cuc. w/175 sacks common-2% Gel.-3% Cal.Cl.

Ordered 130 sacks 50/50 posmix-4% Gel.-3% Cal.Cl. & 8 5/8" plug.

Spot w/drill stem w/heavy mud between all plugs.

1st plug @ 750' w/70 sacks cement

2nd plug @ 250' w/40 sacks cement

3rd plug-solid bridge of hulls & plug @ 40' w/10 sacks cement.

Circulate 10 sacks in ret hole.

RECEIVED
STATE CORPORATION COMMISSION

Very truly yours,

MAR 22 1982

Conservation Division Agent

CONSERVATION DIVISION
Wichita Kansas