



15-051-73060-0000

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Walter Oden of Red Tiger Drlg. Co. has this date requested permission to plug the following described well:

Operator's Full Name: Joe F. Meier Oil Operations

Complete Address: Box 871, Hays, Ks. 67601

Lease Name: G.S.L. West Well No. 2

Location: NE SW NW Sec. 35 Twp. 11 Rge. 18 (E) (W)

County: Ellis Total Depth: 3717'

Abandoned Oil Well Gas Well Input Well SWD Well D&A XXX

Other well as hereafter indicated: _____

Mr. Oden was instructed to plug the well as follows:

8 5/8"-219' S.P. cuc. w/245 sacks common-2% Gel.-3% Cal.Cl.

Ordered 130 sacks 50/50 posmix-4% Gel.-3% Cal.Cl. & 8 5/8" plug.

Spot w/drill stem w/heavy mud between all plugs.

1st plug @ 750' w/70 sacks cement.

2nd plug @ 230' w/40 sacks cement.

3rd plug-solid bridge of hulls & plug @ 40' w/10 sacks cement.

Circulate 10 sacks in rat hole.

Very truly yours,

Phillip R. Dick
Conservation Division Agent
Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JUL 12 1982

CONSERVATION DIVISION
Wichita, Kansas