

State of Kansas



15-051-205-05-0000

ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 OCT 1 1969
 CONSERVATION DIVISION
 Wichita, Kansas

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Herren of Hummon Oil, Inc. has this date requested permission to plug the following described well:

Mr. Herren guarantees payment of the plugging fee.

Operator's full Name: Hummon Oil, Inc.

Complete Address: 821 Union Nat'l Bldg., Wichita, Ks.

Lease Name: Johnson Well No. 1

Location: C SW SW NW Sec. 33 Twp. 13 Rge. (E)(W) 18

County: Ellis Total Depth 3667' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Herren was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 660' and displace
70 sk cmt thru drill pipe. Heavy mud to 240' set cementing plug and
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo J. Massey
 Conservation Division Agent