

State of Kansas



15051-20500-0000

ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 29 1969
 CONSERVATION DIVISION
 Wichita, Kansas

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Norwood of Leben Drlg. has this

date requested permission to plug the following described well:

Mr. Norwood guarantees payment of the plugging fee.

Operator's full Name: Mendo Oil Corporation

Complete Address: 5810 N. Eastern Oklahoma City, Okla.

Lease Name: Johnson Well No. A1

Location: NE NW SW Sec. 33 Twp. 11 Rge. (E)(W) 18

County: Ellis Total Depth 3699' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Norwood was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing pljg at 720' and displace

70 sk cmt thru drill pipe. Heavy mud to 210' set cementing plug and

displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo F. Massey
 Conservation Division Agent