



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAY 15 1973

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Niernbergen of Murfin Drlg. has this
date requested permission to plug the following described well:

Mr. Niernberger guarantees payment of the plugging fee.

Operator's full Name: 617 Union Center Wichita, Ks.

Complete Address: Murfin Drilling Co.

Lease Name: Pulec "B" Well No. 1

Location: C N/2 NW SW Sec. 4 Twp. 11 Rge. (E)(W) 19

County: Ellis Total Depth 3150' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Niernberger was instructed to plug the well as follows:
Gun pits, circulate heavy mud, set cementing plug at 685' and displace
70 sk cmt thru drill pipe. Heavy mud to 185' set cementing plug and
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo F. Massey
Conservation Division Agent