

3-20

4-041891

15051-0034-0000

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15- 8-10-59  
100'E. of  
SW NW NE /4 SEC. 09, 11 S, 18 W  
4290 feet from S section line  
2210 feet from E section line

Operator license# 9067  
Operator: Damar Resources, Inc.  
Address: 234 W. 11th Street  
Hays, Kansas 67601

Lease: Meistrell Well # D-2  
County: Ellis 118.98  
Well total depth 3661 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 252 feet  
w/ 200 sxs.cmt.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cementing License#  
Address: Russell, Kansas 67665

Company to plug at: Hour: 1:00P.M. Day: 20 Month: March Year 1997

Plugging proposal received from: Dean Ives

Company: Damar Resources, Inc. Phone:

Were: 5 1/2" casing set at 3649' w/175 sxs cement. Perfs. at 3267' - 3271'.  
Ordered 325 sxs 60/40 pozmix - 10% gel with 1/4# F.C. plus 600# hulls.  
Salt at 2050' - Anhy. at 1480' - Dakota at 750' - T.O.F. at 300'.  
T.O.C. at 2760' - C.I.B.P. at 3288'.

RECEIVED  
KANSAS CORP COMM  
1997 MAR 27 AM 11:42

Plugging Proposal Received by: Herb Deines  
Plugging operations attended by agent? All [ X ], Part [ ], None [ ]

Completed: Hour: 4:15 P.M., Day: 20, Month: March, Year: 1997

Actual plugging report: R.I.H. with tubing 3250'. Spotted 100 sxs cement with 200# hulls.  
Pulled to 2100'. Spotted 100 sxs cement with 200# hulls. Pulled to 1000'. Spotted 50 sxs  
with 100# hulls to circulate at surface. P.O.O.H. with tubing. Squeezed casing with 10 sxs  
cement. Max. P.S.I. 200#.  
8 5/8" S.P. Squeezed with 60 sxs cement plus 100# hulls. Max. P.S.I. 500#. S.I.P. 200#.

Remarks:  
Condition of casing(in hole): GOOD X BAD  
Bottom plug(in place): YES X, CALC, NO  
Plugged through TUBING X, CASING  
Anhy.plug: YES X NO  
Dakota plug: YES X, NO  
Elevation: 2045 G.L.

I did [ X ] / did not [ ] observe the plugging.

Dennis L. Hamel  
(agent)

INVOICED

DATE 3-27-97

INV. NO. 47821

3-20