

1 060703

API NUMBER 15- 135-22,936-00-00 *R*

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW SE NE, SEC. 27, T 17 S, R 24 W/KX
2970 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5161
Operator: Palomino Petroleum
Name & Address: P. O. Box 18610
Wichita, KS 67218

Lease Name Patricia Well # 1
County Ness 145.37
Well Total Depth 4473 Mississippi feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 250

Abandoned Oil Well Gas Well Input Well SWD Well D&A x

Other well as hereinafter indicated

Plugging Contractor DNB Drilling, Inc. License Number 5476
Address 535 North Oliver, Wichita, KS 67208

Company to plug at: Hour: 5:00 am Day: 31 Month: October Year: 19 85

Plugging proposal received from John Taylor

(company name) DNB Drilling (phone) 316-687-5471
Elevation 2433'

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1742-1774'

- 1st plug at the base of the Anhydrite with 50 sx cement
- 2nd plug 50' below the base of the Cheyenne with 80 sx cement
- 3rd plug 30' below the base of the surface pipe with 40 sx cement
solid bridge
- 4th plug hulls - plug at 40' -- cement to surface with 10 sx cement
- 6th plug to circulate rat hole with 10 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None x

Operations Completed: Hour: 6:30 am Day: 31 Month: October Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1774' with 50 sx cement, 2nd plug at 760' with 80
sx cement, 3rd plug at 280' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -
plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with
10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

NOV 5 1985
11 05 1985
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(if additional description is necessary, use BACK of this form.)

INVOICED (do not) observe this plugging.

Signed *Paul A. Luther*
(TECHNICIAN)

DATE NOV 12 1985

CJV. NO. 10972