

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-01380-00-01  
Spot: CSESESW Sec/Twnshp/Rge: 6-11S-18W  
330 feet from S Section Line, 2310 feet from W Section Line  
Lease/Unit Name: PEAVEY OWWO Well Number: 3  
County: ELLIS Total Vertical Depth: 1005 feet

Operator License No.: 9408  
Op Name: TRANS PACIFIC OIL CORPORATION  
Address: 100 SOUTH MAIN STE 200  
WICHITA, KS 67202

Conductor Pipe: Size feet: 835.00  
Surface Casing: Size 8.625 feet: 255  
Production: Size 5.5 feet: 1005 500 SX CMT  
Liner: Size feet:

Well Type: SWD UIC Docket No: D21400.0 Date/Time to Plug: 07/22/2002 10:00 AM

Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE INC

Proposal Rcvd. from: FRANK BIEKER Company: TRANS PACIFIC OIL CORPORATIO Phone: (316) 262-3596

Proposed Plugging Method: Ordered 150 sxs Multi Density Cement - 400# hulls.  
Perfs 876' - 914'.

Plugging Proposal Received By: PAT STAAB

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 07/22/2002 11:00 AM

KCC Agent: PAT STAAB

Actual Plugging Report:

Swift Cementing Services rigged to casing and pumped 120 sxs cement with 400# hulls.  
Circulated cement out backside.  
Closed off backside and pumped an additional 5 sxs cement.  
Max. P.S.I. 400#. S.I.P. 300#.

RECEIVED  
AUG 06 2002  
KCC WICHITA

Remarks: LEASE ORIGINALLY KNOWN AS RICHARDS #1. SWIFT SERVICES, INC. - TICKET#4752.

Plugged through: CSG

District: 04

Signed [Signature]

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 8-6-02

INV. NO. 2003060176

JUL 26 2002

ROBERT R PRICE OPER CO  
TULSA OK

6-11S-18W  
SE SE SW

#3 PEAVEY OWWO

site: 7-3/4 N & 1 E OF HYACINTH KS	city: ELLIS	API 15-051-01380
contr: RANGER DRILLING	field: ANDRESON SOUTH	
fr date 06/14/82	spd date 08/15/82	drig comp 08/15/82
	card issued 04/28/83	last revised 04/13/98


ELV: 1942 DF SMP  
 tops.....depth/datum  
 ANH.....1294 + 648  
 \*B/ANH.....1330 + 612  
 TOP.....2930 -988  
 HEEB.....3116 -1174  
 LANS.....3158 -1216  
 BKC.....3395 -1453  
 CONG CHT.....3499 -1557  
 SIMP DOL.....3551 -1609  
 SIMP SH.....3556 -1614  
 ARB.....3574 -1632  
 RTD-OLD.....3610 -1668  
 \*DRILLER TOP

IP status:  
 SWDW, CED HILL 876-914, 01/14/83  
 CORR & INFO REL: 4/13/98 - CORR OLD CONTR (WAS  
 IRON DRILLING) & TOPS; ADDED MISC INFO  
 OLD INFO: OPERATOR WAS DARBY & BOTHWELL, (1)  
 RICHARDS, SPD 02/16/45, 03/18/45 12-1/2" 43, 8-5/8"  
 1300, 5-1/2" 3456, D&A, ARB, 03/18/45 (CARD ISSUED  
 09/01/47)  
 CONTR: DONALD T INGLING  
 COMMENT: GD PORO, BUT NO SATR IN ARB; WAS  
 API IOG-1453

COPYRIGHT 1998  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS

(over)

ROBERT R PRICE OPER CO  
TULSA OK

6-11S-18W  
SE SE SW

#3 PEAVEY OWWO

DRLR SD ZNS: 400-430, 740-941  
 SALT ZN: 1560-1800  
 SHOWS: 3171-3174 (LANS LM, SLI STN), 3246-3250 (LANS LM, SLI STN), 3380-3385 (LANS LM, SATR)  
 NO CORES OR TSTS  
 MICT - CO, PF (LKC) 72/3378-3388, SFO, NAT, AC 1000 GAL, SWB 0.5 BOPH, RE-AC 1500 GAL, SWB 1.5 BOPH, RE-AC 4000 GAL, SWB 5 BOPH/3 HRS, FU 1500' FL/18 DAYS, POP, P 27 BF INCL 10 B AC W/5 HRS, P 7.5 BO & TR W/ 2 HRS, P 22.5 BF (SO)/9 HRS, OIL DECRG, WTR INCRG, NO OIL SOLD, DECISION MADE TO P & A 6/4/45  
 NEW INFO: FR 06/14/82, RE-ENTERED 08/15/82 WSH DWN TO 1005 DC 08/15/82 CSG: SET 5-1/2" 1005 MICT - CO, PF (CED HILL) 876-914, COMP AS SWDW - INJECTION RATE SATISFACTORY, 1/14/83

33200

03