

1090169

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-22,586-00-00 ^R

S/2 SE NE, SEC. 26, T 17 S, R 24 (W)

2310 feet from N^{XX} section line

660 feet from ~~W~~E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5038

Lease Name Mishler "A" Well # 1

Operator: Robinson Oil Company

County Ness

Name & Address 737 R. H. Garvey Building

Well Total Depth 4580 148.85 feet

Wichita, KS 67202-2992

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 426

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Allen Drilling Company License Number 5418

Address Box 1389, Great Bend, KS 67530

Company to plug at: Hour: 2:00 am Day: 25 Month: May Year: 19 84

Plugging proposal received from Don Kearn

(company name) Allen Drilling (phone) 316-793-5681

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1770' with 50 sx cement 2nd plug at 1020' with 50 sx cement

3rd plug at 480' with 40 sx cement solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by RBFearlutton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 5:30 am Day: 25 Month: May Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1770' with 50 sx cement, 2nd plug at 1020' with 50

sx cement, 3rd plug at 480' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

15 sx cement.

RECEIVED STATE CORPORATION COMMISSION

JUN 01 1984

06-01-1984 CONSERVATION DIVISION Wichita, Kansas

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Allied # 32645

(if additional description is necessary, use BACK of this form)

INVOICED

(if you did not) observe this plugging.

DATE 6-6-84

Signed RBFearlutton (TECHNICIAN)

INV. NO. 1904

JUN 08 1984

FORM CP-2/3 Rev. 01-84

5-21