

1 050421

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 135-20,674-00-00

C SW SE , SEC. 26 , T 17 S, R 24 W/E

660 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5285

Lease Name Paul "A" Well # 2

Operator: The Dane G. Hansen Trust

County Ness 145.93

Name & Address P. O. Box 187

Well Total Depth 4490 feet

Logan, KS 67646

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 324

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cementing License Number

Address Box 31, Russell, KS 67665

Company to plug at: Hour: 1:00 pm Day: 28 Month: December Year: 19 84

Plugging proposal received from D. G. Bales

(company name) The Dane G. Hansen Trust (phone) 913-689-4816

were: 5 1/2" set at 4488' Perfs at 4470-75' DV set at 1400'

1st plug sand back to 4420' and dump 5 sx cement on top of sand through bailer

2nd plug pump 300 sx common cement down from top

Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 1:50 pm Day: 28 Month: December Year: 19 84

ACTUAL PLUGGING REPORT 5 1/2" set at 4488' Perfs at 4470-75' DV set at 1400'

1st plug sanded back to 4420' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 300 sx common cement down from the top

RECEIVED  
STATE CORPORATION COMMISSION  
01-07-1985  
7 AM 07 1985

Remarks: Used common cement

(if additional description is necessary, use BACK of CONSERVATION DIVISION  
Wichita, Kansas

INVOICED

DATE 1-14-85

INV NO 6420

Signed Richard W. Lacey (TECHNICIAN)