

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-24163-00-00
Spot: CE2W2SW Sec/Twnshp/Rge: 14-17S-24W
1120 feet from S Section Line, 920 feet from W Section Line
Lease/Unit Name: NEYER Well Number: 1-14
County: NESS Total Vertical Depth: 4620 feet

Operator License No.: 31120
Op Name: PELICAN HILL OIL & GAS, INC.
Address: 1401 N EL CAMINO REAL, STE 207
SAN CLEMENTE, CA 92672

Conductor Pipe: Size feet: \$150.15
Surface Casing: Size 8.625 feet: 206
Production: Size feet:
Liner: Size feet:

Well Type: DH UIC Docket No: Date/Time to Plug: 10/20/2001 6:30 AM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: TOM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: 1ST PLUG AT 1830' WITH 50 SX CMT. 2ND PLUG AT 1100' WITH 80 SX CMT. 3RD PLUG AT 500' WITH 40 SX CMT. 4TH PLUG AT 230' WITH 40 SX CMT. 5TH PLUG AT 40' WITH 10 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 10/20/2001 9:15 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

1ST PLUG AT 1830' WITH 50 SX CMT. 2ND PLUG AT 1100' WITH 80 SX CMT. 3RD PLUG AT 500' WITH 40 SX CMT. 4TH PLUG AT 230' WITH 40 SX CMT. 5TH PLUG AT 40' WITH 10 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Remarks: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01

Signed Richard W. Lacey
(TECHNICIAN)

RECEIVED

OCT 29 2001
10-29-2001
KCC WICHITA

INVOICED

DATE 10-30-01
INV. NO. 2002060875

OCT 22 2001

Form 10-2/3