

1 030407

API NUMBER 15- 135-20,868-00-00 *R*

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C NE NE, SEC. 9, T 17 S, R 24 W/E
4620 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5245

Lease Name Phelps Well # 1

Operator: Okmar Oil Company

County Ness 144.33

Name & Address 970 Fourth Financial Center

Well Total Depth 4441 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 250 ✓

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 10:00 am Day: 19 Month: April Year: 1985

Plugging proposal received from Ronnie Hoover

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" at 4437' Perfs at 4422-26, 4434-37, 4428-34'

1st plug sand back to 4370' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, and 150 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
04-23-1985
APR 23 1985

Plugging Proposal Received by Paul A. Luthi

CONSERVATION DIVISION
Wichita, Kansas

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 11:30 am Day: 19 Month: April Year: 1985

ACTUAL PLUGGING REPORT 1st plug sanded back to 4370' and dumped 5 sx cement on top of

sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement,

10 sx gel, 1 sack hulls, and 150 sx cement

Maximum pressure 500 psi and shut in 100 psi

Remarks: Recovered 3229' 5 1/2" casing. Used 60/40 Pozmix 2% gel 3% cc by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 5-3-83

INV. NO. 7935

Signed *Steve Courant*
(TECHNICIAN)