

090260

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-135-22,732-00-00 ✓

SE NW SW, SEC. 26, T 17 S, R 24 W/E  
1650 feet from X section line  
4290 feet from X section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6177

Lease Name Schreiber Well # D-1

Operator: Foxfire Exploration, Inc.

County Ness

Name & Address P. O. Box 6360

Well Total Depth 4490 145.73 feet

Los Osos, CA 93402

Conductor Pipe: Size \_\_\_\_\_ feet

\_\_\_\_\_

Surface Casing: Size 8 5/8 feet 335

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Foxfire Drilling Co., Inc. License Number 8430

Address Box 133, Wakeeney, KS 67672

Company to plug at: Hour: 3:00 pm Day: 10 Month: December Year: 19 84

Plugging proposal received from Gary Fisher

(company name) Foxfire (phone) 913-743-5337

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1740' with 50 sx cement,

2nd plug at 1020' with 50 sx cement

3rd plug at 390' with 40 sx cement  
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by RBFarhutan  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 6:45 pm Day: 11 Month: December Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1740' with 50 sx cement, 2nd plug at 1020' with 50  
sx cement, 3rd plug at 390' with 40 sx cement, 4th & 5th plugs - solid bridge- hulls -  
plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with  
15 sx cement.

Remarks: Used 60/40 Pozmix 2% gel 3% cc

(If additional description is necessary, use BACK of form.)

I did / did not) observe this plugging.

DATE 12-26-89

INV. NO. 61687

Signed RBFarhutan  
(TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 18 1989  
CONSERVATION DIVISION  
Wichita, Kansas

2

CARD MUST BE TYPED

State of Kansas  
**NOTICE OF INTENTION TO DRILL**  
(see rules on reverse side)

CARD MUST BE SIGNED

Starting Date: November 26 1984  
month day year

API Number 135-22,732-00-00

OPERATOR: License # 6177  
Name Foxfire Exploration, Inc.  
Address P. O. Box 6360  
City/State/Zip Los Osos, CA 93402  
Contact Person D. C. Marchant  
Phone (805) 528-6008

SE NW SW  East  
SW  West  
Sec 26 Twp 17 S. Rge 24  
.....1650..... Ft North from Southeast Corner of Section  
.....4290..... Ft West from Southeast Corner of Section  
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 8430  
Name Foxfire Drilling Co., Inc.  
City/State WaKeeney, Kansas

Nearest lease or unit boundary line .....330..... feet.  
County Ness  
Lease Name Schreiber Well# D-1  
Domestic well within 330 feet:  yes  no  
Municipal well within one mile:  yes  no

Well Drilled For: Well Class: Type Equipment:  
 Oil  Swd  Infield  Mud Rotary  
 Gas  Inj  Pool Ext.  Air Rotary  
 OWWO  Expl  Wildcat  Cable

Depth to Bottom of fresh water .....75..... feet  
Lowest usable water formation Dakota  
Depth to Bottom of usable water .....970..... feet  
Surface pipe by Alternate: 1  2   
Surface pipe to be set .....320..... feet  
Conductor pipe if any required NA..... feet  
Ground surface elevation .....2446..... feet MSL.  
This Authorization Expires 5-19-85  
Approved By [Signature] 11-19-84

If OWWO: old well info as follows:  
Operator .....  
Well Name .....  
Comp Date ..... Old Total Depth .....  
Projected Total Depth 4500..... feet  
Projected Formation at TD Mississippian  
Expected Producing Formations Mississippian

I certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C.C. specifications.

Date 11/13/84 Signature of Operator or Agent [Signature] Title ..... Owner .....  
Set 320 of 8 5/8 ch 12/3/84 MHC/UCHE 11/19/84

RECEIVED  
STATE COMPARATION COMMISSION  
DEC 16 1984  
CONSERVATION DIVISION  
Wichita, Kansas  
12-18-1984