

To: 1 051715 8-26  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-135-23722-00-00  
NE SE, SEC. 36, T. 17 S, R. 24 W/EX  
1980 feet from S section line  
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5086  
Operator: Pintail Petroleum Ltd.  
Name & Address: 412 E. Douglas, Ste. 1  
Wichita, KS 67202

Lease Name Yost "A" Well # 1  
County Ness  
Well Total Depth 4397 142.90 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 350

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Plains Inc. License Number 4072

Address P.O. Box 346, Ness City, KS 67560-0346

Company to plug at: Hour: 10 a.m. Day: 26 Month: 8 Year: 19 93

Plugging proposal received from Flip Phillips

(company name) Pintail Petroleum Ltd. (phone) 316-263-2243

Work: 4 1/2" at 4380' w/300 sx cement, Open hole 4380-97'

1st plug sand back to 4330' and dump 4 sx cement on top of sand through bailer, line

2nd plug pump 50 sx cement at 1650'

3rd plug pump 80 sx cement at 1050'

4th plug pump 40 sx cement at 380', 5th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2 p.m. Day: 26 Month: 8 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 4330' and dumped 4 sx cement on top of sand through bailer,

2nd plug at 1650' with 50 sx cement,

3rd plug at 1050' with 80 sx cement,

4th plug at 380' with 40 sx cement,

5th plug at 40' with 10 sx cement. Gel spacers between plugs.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2275' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE: 9-9-93

INV. NO. 385-78

Signed Richard M. Lacy (TECHNICIAN)

RECEIVED STATE CORPORATION COMMISSION

AUG 30 1993 CONSERVATION DIVISION Wichita, Kansas