

To: 1 120974 9-28
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-22,373-00-00
SE NW NW, SEC. 36, T 17 S, R 24 W/E
4290 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 4011
Operator: Ummels Tank Service
Name & Address Box 37
Brownell, KS 67521

Lease Name Ummel Well # 1
County Ness 144.95
Well Total Depth 4460 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 350

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____
Plugging Contractor Ummels Tank Service License Number 4011
Address Box 37, Brownell, KS 67521

Company to plug at: Hour: 10 a.m. Day: 28 Month: 9 Year: 19 94

Plugging proposal received from Dean Ummel
(company name) Ummels Tank Service (phone) 913-481-2316

were: 4 1/2" at 4460' w/200 sx cement, PBD 4430', Perfs at 4407-11'
4 1/2" casing previously squeezed at 1257'
1st plug pump 1 sx hulls and 20 sx cement to 4300'
2nd plug perforate at 1100' and pump 300 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:30 p.m. Day: 28 Month: 9 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4300'. Pressured casing to 400#.

2nd plug perforated 4 1/2" casing and pumped in 4 1/2" casing with 150 sx cement. Cement did not circulated. Had slight circulation.

3rd plug pumped in 8 5/8" X 4 1/2" annulus with 100 sx cement. Pumping pressure on 4 1/2" casing 0-500 psi and shut in 200 psi. Pumping pressure on 8 5/8" X 4 1/2" annulus in 200 psi.

Remarks: Used 65/35 Pozmix 6% gel by Allied. No casing recovery.
(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

INVOICED
DATE 10-10-94
INV. NO. 41391
9-28

Signed Dean Ummel
(TECHNICIAN)

PAID
0-500
CORPORATION COMMISSION
10-04-1994
OCT 04 1994