

1 030601

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-21,515 -00-00-
150' W of NW NE NW, SEC. 31, T 17 S, R 24 (W) X

TECHNICIAN'S PLUGGING REPORT

Operator License # 5161

Operator: Palomino Petroleum
Name & Address: P. O. Box 18610
Wichita, KS 67218

4950 feet from S section line
3780 feet from E section line

Lease Name Weeks Well # 1

County Ness 143.39

Well Total Depth 4412 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 244

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 5:00 pm Day: 2 Month: December Year: 19 85

Plugging proposal received from Neil Peddicord

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 4403' PBSD 4395' Perfs at 4302-05'

1st plug sand back to 4250' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 12 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 175 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 7:30 pm Day: 2 Month: December Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4110' and dumped 4 sx cement on top of sand through bailer. 11-21-85 - pumped 3 sx hulls, 15 sx gel, 2 sx cement - cement

circulated up back side - wash-out - will plug with tubing.

12-2-85 - Pumped through tubing with heavy mud between plugs - pumped 10 sx gel and 50 sx cement at 1710', pumped 12 sx gel and 70 sx cement at 1020', pumped 5 sx gel and 40 sx cement at 270', pumped 10 sx cement at 30'.

Remarks: Recovered 2100' 4 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

Dan Goodrow observed the plugging
(If additional description is necessary, use BACK of this form.) observe STATE CORPORATION COMMISSION

INVOICED RECEIVED
DEC 16 1985

DATE

INV. NO. 11529

12-2

DEC 5 1985
12-05-1985
CONSERVATION DIVISION
Wichita, Kansas

Signed Steve Durrant (TECHNICIAN)