

1051028

3-24-88

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-21,426-00-00

NE NW NW, SEC. 29, T 17 S, R 24 W 5E

4950 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8778

Lease Name Keilman "B" Well # 1

Operator: Midwestern Supply Company, Inc.
Name &

County Ness 142.77

Address Box 1633
Great Bend, KS 67530

Well Total Depth 4393 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 274

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 10 a.m. Day: 24 Month: 3 Year: 1988

Plugging proposal received from Clay Duntz

(company name) Kelso Casing Pulling, Inc. (phone) 316-792-6605

were: 4 1/2" at 4387' Perfs at 4326-29, 4226-31'

1st plug sand back to 4175' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 125 sx cement.

Plugging Proposal Received by James R. Kapp
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:20 a.m. Day: 24 Month: 3 Year: 1988

ACTUAL PLUGGING REPORT 1st plug sanded back to 4175' and dumped 4 sx cement on top of
sand through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 125
sx cement.

Maximum pressure 500 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2200' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

MAR 28 1988
03-28-1988
RECEIVED
CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 3-29-88
INV. NO. 20847

Signed Richard W. Lacy
(TECHNICIAN)