

1 061149

10-21

API NUMBER 15- 135-21,386 -00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NW NW NE, SEC. 29, T 17 S, R 24 W/E  
4950 feet from S section line  
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9615 RECEIVED  
Lease Name Gerstner "B" Well # 1

Operator: Joe Gerstner Oil STATE CORPORATION COMMISSION  
Name: County Ness 141.80

Address Box E  
Well Total Depth 4363 feet

Ness City, KS 67560  
Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 279

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor: Rockhold Engineering, Inc. License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 10:30 a.m. Day: 21 Month: 10 Year: 19 88

Plugging proposal received from Jim Rockhold

(company name) Rockhold Engineering, Inc. (phone) 316-792-2506

were: 4 1/2" at 4362' PBD 4351' Perfs at 4239-43'

1st plug sand back to 4190' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper

plug and pump 150 sx cement.

Plugging Proposal Received by Duane Rankin  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 11:30 a.m. Day: 21 Month: 10 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4190' and dumped 4 sx cement on top of  
sand through bailer,

2nd plug pumped 3 sx hulls, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8" wiper

plug and pumped 150 sx cement.

Maximum pressure 800 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1152' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED

(If desired, check box to observe this plugging.)

DATE 10-28-88

Signed Paul A. Luthi  
(TECHNICIAN)

INV. NO. 22831