

1050288

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-22,274-00-00
SW NW SW, SEC. 29 ; T 17 S, R 24 W/E

_____ feet from N/S section line
_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5087

Lease Name _____ Weeks _____ Well # 1-29

Operator: Texas Energies, Inc.

County _____ Ness

Name & Address P. O. Box 947

Well Total Depth 4555 148.04 feet

Pratt, KS 67124

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 369 380

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 1:00 pm Day: 18 Month: July Year: 19 84

Plugging proposal received from Neil Petticord

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" set at 4530' DV tool at 4424' Perfs 4410-13'

1st plug sand back to 4360' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

release 8 5/8" rubber plug and pump an additional 150 sx cement

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:45 pm Day: 18 Month: July Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2" set at 4530' DV tool at 4424' Perfs 4410-13'

1st plug sanded back to 4360' and dumped 4 sx cement on top of sand through bailer

2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

released 8 5/8" rubber plug and pumped an additional 150 sx cement.

Maximum pressure 900 psi and shut in pressure 200'psi

Remarks: They recovered 2500' of 4 1/2" casing. Used 60/40 Pozmix 2% gel 3% c/wichita, Kansas
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 7-27-84

INV. NO. 2703

Signed Richard W. Lacey
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
JUL 24 1984
07-24-1984
CONSERVATION DIVISION
Wichita, Kansas