

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-24141-00-00
Spot: S2SWNW Sec/Twnshp/Rge: 28-17S-24W
2970 feet from S Section Line, 510 feet from W Section Line
Lease/Unit Name: DEPPERSCHMIDT Well Number: 1-28
County: NESS Total Vertical Depth: 4470 feet

Operator License No.: 6569
Op Name: SCHMITT, CARMEN, INC.
Address: PO BOX 47
GREAT BEND, KS 67530

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 219
Production: Size _____ feet:
Liner: Size _____ feet:

\$145.28

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 07/12/2001 6:30 PM
Plug Co. License No.: 5184 Plug Co. Name: SHIELDS OIL PRODUCERS INC
Proposal Rcvd. from: BURT Company: SHIELDS OIL PRODUCERS INC Phone: (785) 483-3141

Proposed Plugging Method: 1ST PLUG AT 1700' WITH 50 SX CMT. 2ND PLUG AT 1000' WITH 50 SX CMT. 3RD PLUG AT 500' WITH 40 SX CMT. 4TH PLUG AT 230' WITH 40 SX CMT. 5TH PLUG AT 40' WITH 10 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 07/12/2001 9:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

1ST PLUG AT 1700' WITH 50 SX CMT. 2ND PLUG AT 1000' WITH 50 SX CMT. 3RD PLUG AT 500' WITH 40 SX CMT. 4TH PLUG AT 230' WITH 40 SX CMT. 5TH PLUG AT 40' WITH 10 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

INVOICED
DATE 7-17-01
VV. NO. 2002060074

Remarks: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01

RECEIVED
KANSAS CORPORATION COMMISSION

Signed Michael Maier

(TECHNICIAN)

JUL 13 2001

JUL 17 2001
07-17-2001
CONSERVATION DIVISION

