

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-051-19450-0001

NW, SEC. 20, T 11 S, R 18 W 1/4

1650 FEET FROM N 1/8 SECTION LINE

2310 FEET FROM W 1/8 SECTION LINE

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # 6273

LEASE NAME Frisbie WELL # 1

OPERATOR: Robert R. Price
NAME & ADDRESS Box 45442, Tulsa, Ok.
74145

COUNTY Ellis

WELL TOTAL DEPTH 3616 \$117.52 FEET

CONDUCTOR PIPE: SIZE _____ FEET _____

SURFACE CASING: SIZE 8 5/8" FEET 1252'

ABANDONED OIL WELL X GAS WELL _____ INPUT WELL _____ SWD WELL _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR Kelso Casing Pulling LICENSE NUMBER 6050

ADDRESS Box 176, Chase, Ok. 67524

COMPANY TO PLUG AT: HOUR: 9:00AM DAY: 1 MONTH: 7 YEAR: 1983

PLUGGING PROPOSAL RECEIVED FROM Michael Kelso

(COMPANY NAME) Kelso Casing Pulling (PHONE) 316-938-2457

WERE: Order 165 lbs. 50 permix - 4% Gel, 3% Latex, 15 lbs. Gel, 5 lbs. Hulls & 8 5/8" plug

PLUGGING PROPOSAL RECEIVED BY G. H. J. Schick
(TECHNICIAN)

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART _____ NONE _____

OPERATIONS COMPLETED: HOUR: 1:30 PM DAY: 1 MONTH: 7 YEAR: 1983

ACTUAL PLUGGING REPORT 8 5/8" - 1252' w/ 600 lbs. 5 1/2" set at 3615 w/ 200 lbs.

Plug back to 3612'. Top perf. at 2975'. Plugged bottom w/ 5 lbs. cement, sand & 5 lbs. cement to 2900'. Shot pipe 1 time & recovered 2916'. Pumped in 8 5/8", 4 lbs. hulls, 12 lbs. Gel, 65 lbs. cement, 3 lbs. Gel, 1 lb. hulls, released plug & followed w/ 100 lbs. cement w/ 500 pounds pressure.

REMARKS: Elev. 1955'
Cemented By Allied Cementing Co. Inc.

I (DID / ~~DID NOT~~) OBSERVE THIS PLUGGING.

INVOICED

DATE 7-19-83

INV. NO. 4878-W

RECEIVED SIGNED
STATE CORPORATION COMMISSION

G. H. J. Schick
(TECHNICIAN)

JUL 11 1983

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
REV. 6-83