

4 060228

7-11 15:051-30643-0001 2625
API NUMBER 15-11-19-68 OWWO 15,061

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE SW NE SEC. 20, T 11 S, R 18 W/E

2970 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5004

Lease Name Wasinger Well # 2

Operator: Vincent Oil Corporation
Name & Address 100 N. Main #500

County Ellis 35.40

Well Total Depth 970 feet

Wichita, KS

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 162

Abandoned Oil Well Gas Well Input Well SWD Well XXXX D&A

Other well as hereinafter indicated

Plugging Contractor Co tools License Number

Address

Company to plug at: Hour: 10:00AM Day: 11 Month: July Year: 1991

Plugging proposal received from Pat Livingston

(company name) Vincent Oil Corporation (phone)

were: Order 50 sxs. Common cement and 200 sxs. 60/40pos 8%gel and hulls.

Note: On 5-3-91 well cleaned out to to base of anhydrite 1370-1406' and cemented to 970' with cement through tubing. Well would not pressure up enough to pass MIT so decision made to plug well. Perfs at 970-80 & 1000 to 10'

Plugging Proposal Received by Herb Deines (TECHNICIAN)

Plugging Operations attended by Agent?: All XXXXXX Part None

Operations Completed: Hour: 10:45AM Day: 11 Month: July Year: 19 91

ACTUAL PLUGGING REPORT 8 5/8" to 162', 5 1/2" 3626'. Squeezed from 826' to surf. with 143 sxs. PBD 970'. Tied onto production casing and pmp 50 sxs. common cement, 125 sxs 60/40pos 8%gel with no hulls and 75 sxs. 60/40pos 8%gel with 250# hulls. Max 350# SIP 300#.

RECEIVED STATE CORPORATION COMMISSION

JUL 30 1991

CONSERVATION DIVISION Wichita, Kansas

Remarks: B-I Services (If additional description is necessary, use BACK of this form.)

INVOICED (do not observe this plugging.)

DATE 8-13-91

INV. NO. 32696

Jib. S.

Signed Herb Deines (TECHNICIAN)

Herb Deines