

4-050252

10-21

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-051-21,015-0000

SW SW SW /4 SEC. 20, 11 S, 18 W
330 feet from S section line
4950 feet from E section line

Operator license# 9860

Lease: Hand Well # 4

Operator: Castle Resources, Inc.

County: Ellis 117.71

Address: 1200 E. 27th Street
Hays, Kansas 67601
913-625-5155

Well total depth 3622 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 423 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cementing License#

Address:

Company to plug at: Hour: A.M. Day: 21 Month: October Year: 1996

Plugging proposal received from: Jerry Green

Company: Phone:

Were: Order 275 sxs 60/40 pozmix - 10% gel - 600# hulls - 13 sxs gel.
Elevation 2095' - 8 5/8" set at 423' w/300 sxs. - 5 1/2" set at 3622' w/150 sxs.
Perfs 3101' - 3400'. Anhydrite 1394'.

RECEIVED
KANSAS CORP COMM
OCT 29 1996

Plugging Proposal Received by: Dennis Hamel

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour 12:00 P.M., Day: 21, Month: October, Year: 1996

Actual plugging report: Perforated 5 1/2" casing at 2050' - 1420' - 795'. Pumped 40 sxs cement and 300# hulls down casing, followed with 13 sxs gel. Squeezed 175 sxs cement and 200# hulls down casing. Tied onto backside and squeezed with 60 sxs cement and 100# hulls. Max. P.S.I. 500#. S.I.P. 350#.

Remarks:

Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING. Elevation: 2095 GL

I did [X] / did not [] observe the plugging.

Martin Miller (agent)

Form CP-2/3

INVOICED
DATE OCT 29 1996
INV. NO. 46844
10-21